



NOTES:

1. RACK HAS SWIVEL CASTORS, LEVELLING FEET, AND SEISMIC BRACE COMBINATION.
2. ALL FLOOR HEIGHTS ARE WITH CASTORS TOUCHING THE FLOOR. LEVELLING FEET ALLOW CASTORS TO RAISE 3/16" MAXIMUM.
3. TUBES FOR FORKLIFT BLADES: 5.80" x 2.00" I.S TUBING ON 18.17" CENTERS.

Dimensional Drawing —

Note: Unless otherwise specified, dimensions are nominal values in inches.